

Tixi Alarm Modem + TILA2 for Mitsubishi Alpha XL Access

QI-TMAL2-EN, V1.2
May 04, 2009

1 Working setup examples

The following setup configurations have been successfully tested.

- Tixi HSM to Tixi HM/HG

1.1 Remote Transmode

AL-PCS/WIN-E:

COM Port setting: COMx (not Modem!)

Remote side:

Alpha XL: GSM and serial communication: other

Alpha XL connected to HM/HG COM1 or COM2 (using GSM-CAB)

TILA2-Settings:

Connection: "PLC - via telephone line"

AT init: empty

PLC:

COM-Port: COM1 or COM2

Baudrate: 9600

Data Bits/Parity/Stop Bits: 8N1

Handshake: Deactivate DTR

1.2 Local Transmode

AL-PCS/WIN-E:

COM Port setting: COMx (not Modem!)

Remote side:

Alpha XL: GSM and serial communication: other

Alpha XL connected to HM/HG COM2 (using GSM-CAB)

TILA2-Settings:

Connection: "PLC – local at the Alarm Modem"

PLC:

COM-Port: COM2

Baudrate: 9600

Data Bits/Parity/Stop Bits: 8N1

Handshake: Deactivate DTR

Keptime: at least 15s (60s recommended)